

OREGON CORNER RESTORATION FORM

SECTION 21 TOWNSHIP 4N RANGE 28 E

P-9

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

West 1/4 Corner

CONDITION REPORT ONLY

- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed by Taft in 1860 under Contract #93. He set post in mound with trench, and pits and deposited a pint of charcoal. In 1979 survey for Ferguson, I set a 1/2" rebar at 1/4 corner. It was 11.80 feet West of one I set by single proportion in 1978 from wrong Section corner.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 1/2" rebar S 3° 19' W 9.52 feet from the corner.

MONUMENT DETAIL

SKETCH

T4N R28E

1/4
20 21

1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion, I set a 2 3/8" Brass Cap, stamped as above, on a 1" x 30" Iron pipe 0.5 feet below surface of graveled road. See my County Survey #1991-2.

NEW ACCESSORIES From which


- An Alum. tag #951 in RR tie Bears N 64° 32' 10" W 32.97 feet with Bearing Object sign attached.
- An Alum. tag #951 in Power pole Bears S 31° 43' 10" W 35.13 feet with Bearing Object and Witness signs attached.
- An Alum. tag #951 in RR tie fence post Bears S 60° 08' 20" E 57.81 feet with Bearing Object sign attached.
- A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, 0.3 ft. above surface bears S 89° 06' 10" E 25.11 ft.
- Drove steel fence post with Witness sign attached.

LOCATION & COMMENTS


From intersection of Feedville Road and Keller Road, go North 1/2 mile on Keller Rd. to Corner.

SURVEYOR'S SEAL

COMPASS DEC.
 FIRM EDWARDS SURVEYING
 P.O. BOX 763, HERMISTON,
 OREGON, 97838
 PARTY CHIEF D. EDWARDS
 NOTES
 WITNESS S. BENEFIT



G. Dennis Edwards



RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KE

No. 92-45-C