

OREGON CORNER RESTORATION FORM

SECTION 22 TOWNSHIP 4N RANGE 28 E

R-15

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

South 1/4 Corner

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source  
Nothing found.

MONUMENT DETAIL

SKETCH

T4N R28E  
22  
1/4  
27  
1991  
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 2 3/8" Brass Cap on a 1" x 16" Iron pipe, stamped as above, 0.2 foot. below surface of paved road in 5" P.V.C. and in an Alum. Umatilla County Monument Box. See my County Survey #1991-2.

NEW ACCESSORIES From which

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears North 28.59 feet.  
An Alum. tag #951 in RR tie fence corner Bears N 10° 52' W 32.19 feet with Bearing Object sign attached.  
An Alum. tag #951 in Power pole Bears S 9° 05' W 33.06 feet with Bearing Object sign attached.  
A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears South 33.00 feet.

LOCATION & COMMENTS

From intersection of Feedville Road and Hinkle Road, go West on Feedville Rd. 0.5 mile to Corner.

SURVEYOR'S SEAL

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838  
PARTY CHIEF D. EDWARDS  
NOTES  
WITNESS S. BENEFIT

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1871  
G. DENNIS EDWARDS  
951

RECEIVED BY

Umatilla County Surveyor

Date 4-9-92

Rec'd By KR

No. 92-45-C