

OREGON CORNER RESTORATION FORM

SECTION 28 TOWNSHIP 4N RANGE 28

V-13

COUNTY: UMATILLA DATE 11/91

CORNER DESIGNATION

SE Corner

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post, made mound and deposited a pint of charcoal. Krumbein set Brass Cap from RR ties in a 1976 survey for UPLAND INDUSTRIES.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found, Krumbein's 2 1/2" Brass Cap on a 1" Iron pipe, stamped as below.

MONUMENT DETAIL

SKETCH

28 27  
 33 34  
 T4N R28E  
 1976  
 RLS 933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Drove a steel fence post with Witness sign attached, 2 feet East.

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 67° 24' E 66.14 feet, attached Bearing Object sign.  
 Center of West 6" Gate post Bears N 22° 36' E 9.97 feet.  
 An Alum. tag #951 in Power pole Bears S 86° 45' W 21.10 feet, with Bearing Object sign attached.  
 An Alum. tag #951 in RR tie fence post Bears S 65° 40' W 22.97 feet, with Bearing Object sign attached.

LOCATION & COMMENTS

Corner lies 300 ± feet East of Simplot Scale House and 300 ± feet South of Simplot Guard Shack.

COMPASS DEC.

FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838

PARTY CHIEF D. EDWARDS

NOTES

WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
 JULY 16, 1971  
 G. DENNIS EDWARDS  
 951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C