

OREGON CORNER RESTORATION FORM

SECTION 27 TOWNSHIP 4N RANGE 28 E

V-15

COUNTY: UMATILLA DATE 11/91

CORNER DESIGNATION

South 1/4 Corner

CONDITION REPORT ONLY

NOT FOUND

RENEWED

UNRECORDED

x SURVEYED IN

x REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed under Contract #93 by Taft in Oct. 1860. He set post. In a 1976 Survey for UPLAND INDUSTRIES, Krumbein set a Brass Cap from RR ties.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found Krumbein's 1976 2 1/2" Brass Cap on 1" Iron pipe, Badly bent 16" below the surface of a cultivated field 21.63 feet West of my proportioned corner. I did not use Krumbein's corner because it does not fit Taft's distances well nor does it fit a fence line running North from the Center 1/4 of Section 34 as well as the proportioned corner.

MONUMENT DETAIL

SKETCH

T4N R28E  
27  
1/4  
34  
1991  
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 2 3/8" Brass Cap, stamped as above, on a 1" x 30" iron pipe 2.1 feet below surface of a cultivated field. See My County Survey #1991-2.

NEW ACCESSORIES From which

An Alum. tag #951 in RR tie fence post Bears N 24° 13' 20" W 239.70 feet, with Bearing Object sign attached.

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951 Bears N 89° 29' 45" W 32.82 feet. Attached Witness sign to fence.

An Alum. tag #951 in RR tie fence post Bears S 10° 15' 30" E 294.24 feet, with Bearing Object sign attached.

Center of pivot Bears N 70° 39' 30" E 473.06 feet.

LOCATION & COMMENTS

From the Guard shack at "SIMPLOT POTATO PLANT" entrance, go East 1/2 mile. Corner lies 300 feet southerly of holding ponds.

COMPASS DEC.

FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838

PARTY CHIEF D. EDWARDS

NOTES

WITNESS S. BENEFIT

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-e

SURVEYOR'S SEAL

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951