

OREGON CORNER RESTORATION FORM

SECTION 27 TOWNSHIP 4N RANGE 28 E

V-17

COUNTY: UMATILLA DATE 11/91

CORNER DESIGNATION

SE Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed under Contract #93 in October 1860 by Taft. He set post.

MONUMENTS & ACCESSORIES FOUND: Condition and Source
Nothing found.

MONUMENT DETAIL

SKETCH

T4N R28E
27 26

34 35
1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By double proportion I set a 2 3/8" Brass Cap, stamped as above, on a 1" x 30" Iron pipe 1.9 feet below the surface of a cultivated field. See my County Survey #1991-2.

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 64° 28' W 505.5 feet, with Bearing Object sign attached.
A Brass Cap, stamped W.C. LS 951, Bears N 89° 29' 45" W 392.05 feet 0.3 feet above surface with steel fence post and Witness sign 2 feet West.
Center pivot Bears N 77° 00' E 349.50 feet.
Center of 6" Test well casing Bears N 24° 55' 10" W 628.00 feet.

LOCATION & COMMENTS

From the Guard shack at "SIMPLLOT POTATO PLANT" entrance, go Easterly along RR tracks 1 mile. Corner lies 350 feet Westerly of center pivot.

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KR

No. 92-45-C