

OREGON CORNER RESTORATION FORM

SECTION 25 TOWNSHIP 4N RANGE 28 E

V-25

COUNTY: UMATILLA DATE 11/91

CORNER DESIGNATION

SE Corner

CONDITION REPORT ONLY
NOT FOUND
RENEWED
UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in Oct. 1860 under Contract #95. W.B. Campbell set post, drove charred stake and made pits and mounds.

In a 1980 Survey for the County, Krumbein set a 2 1/2" Brass Cap stamped as below, in place of a 2" Iron pipe of unknown origin.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found Krumbein's 1980 2 1/2" Brass Cap.

MONUMENT DETAIL

SKETCH

T4N
R28E R29E

25 30

36 31
1980
RLS 933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Drove a steel fence post with Witness sign, 2 feet East of corner.

NEW ACCESSORIES From which

An Alum. tag #951 in Telephone pole Bears N 43° 02' 40" E 157.85 feet.

An Alum. tag #951 in Power pole Bears N 27° 10' 30" E 76.80 feet.

An Alum. tag #951 in RR tie fence post Bears N 36° 27' W 18.22 feet.

An Alum. tag #951 in 6" Locust fence post Bears S 3° 32' W 13.11 feet.

Attached Bearing Object signs on all of the above.

LOCATION & COMMENTS

From Coe St. RR crossing in Stanfield, go westerly along southerly side of RR tracks 1.5 miles. Corner lies just East of a N-S fence line.

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS

NOTES
WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KR

No. 92-45-9