

OREGON CORNER RESTORATION FORM

SECTION 28 TOWNSHIP 4N RANGE 28E

V-9

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

SW Corner

CONDITION REPORT ONLY
NOT FOUND
RENEWED
UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post, made pits and mound and deposited 1 pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found.

MONUMENT DETAIL

SKETCH

T4N R28E
29 28

32 33
1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By double proportion, I set 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped as above, flush in ground. Drove steel fence post with Witness sign attached, 1.5 feet North. See my County Survey 1991-2.

NEW ACCESSORIES From which

A 1 1/4" x 32" rebar with Alum. tag #951 Bears East 16.04 feet.
A 1" x 30" tubing Bears West 16.38 feet, stamped #951 on North side.
A 5/8" x 30" rebar with Alum. tag #951 Bears South 13.24 feet.
The NW corner of a 30' x 30' metal garage Bears S 23° 51' 20" E 253.20 feet.

LOCATION & COMMENTS

From South end of Butter Creek Hwy. Bridge over Umatilla River, go West on graveled rd. 1/2 mile to Corner.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd By _____

No. 92-45-C