

OREGON CORNER RESTORATION FORM

SECTION 23 TOWNSHIP 4 NORTH RANGE 29 EAST P-17

COUNTY : UMATILLA DATE 8-98

CORNER DESIGNATION

WEST 1/4

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.


ORIGINALLY SURVEYED IN 1861 BY DAVENPORT UNDER CONTRACT #101. HE SET A POST IN A MOUND OF EARTH AND A CHARRED STAKE..

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

NOTHING

SKETCH

MONUMENT DETAIL



MONUMENT SET (PROCEDURES AND DESCRIPTION)

BY SINGLE PROPORTION I SET A 1" X 30" IRON PIPE WITH A 2 3/8" BRASS CAP STAMPED AS ABOVE.

NEW ACCESSORIES FROM WHICH

AN ALUMINUM TAG #951 ON A POWER POLE LIES N 3°.10'00" W, 62.33 FEET.
AN ALUMINUM TAG #951 IN A LOCUST 9" LOCUST TREE LIES S 81°.54'00" W, 19.17 FEET.
AN ALUMINUM TAG #951 IN A RXR TIE BRACE POST LIES S87°.55'17" E, 5.24 FEET.
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES S 87°.55'17" E, 19.38 FEET.

LOCATION AND COMMENTS

COMPASS DEC.

SURVEYOR'S SEAL

FIRM/AGENCY
EDWARDS SURVEYING
P.O. BOX 763
HERMISTON, OREGON 97838
97838

PARTY CHIEF
D. EDWARDS

NOTES

WITNESS
RICK SMITH

RECEIVED BY
Umatilla County Surveyor
Date 10-98
Rec'd By RK
No. 98-213-C

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/99