

OREGON CORNER RESTORATION FORM
SECTION 24 TOWNSHIP 4N RANGE 28
COUNTY: UMATILLA DATE 11/91

R-25

CORNER DESIGNATION

SE Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Campbell under Contract # 95.
He set post, drove a charred stake and raised mound.
In 1954, Higgins set a 1/2" Iron rod.
In 1980, Krumbein set a 2 1/2" Brass Cap on 1" Iron pipe in
place of Higgin's Iron rod and 2 1/2" Brass Cap Witness
Corners Northeast and Southeast.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found Krumbein's 2 1/2" Brass Cap, stamped as below, 4" below
surface of paved road.
Found 2 1/2" B.C. on 1" Iron pipe N 49° 27' E, 38.57 feet,
stamped N E 38.50.
Found 2 1/2" B.C. on 1" Iron pipe S 37° 25' E, 45.03 feet,
stamped S E 45.00.

MONUMENT DETAIL

SKETCH

T4N
R28E R29E
24 19
25 30
1980
RLS 933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 40° 02' E 46.34 feet.
An Alum. tag #951 in Power pole Bears N 22° 17' W 53.32 feet.
Attached Bearing Object signs to all of the above.

LOCATION & COMMENTS

At the intersection
of Feedville and
Ott Roads.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor
Date 4-92
Rec'd By KK
No. 92-45-C