

OREGON CORNER RESTORATION FORM

SECTION 36 TOWNSHIP 4 NORTH RANGE 29 EAST Z-25

COUNTY : UMATILLA DATE 8-98

CORNER DESIGNATION

SE CORNER

— CONDITION REPORT ONLY
— NOT FOUND
— RENEWED
— UNCOVERED
 SURVEYED IN
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.


ORIGINALLY SURVEYED IN 1859 BY GATES UNDER CONTRACT #84. HE SET A POST IN A MOUND OF EARTH.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

NOTHING

SKETCH

MONUMENT DETAIL



MONUMENT SET (PROCEDURES AND DESCRIPTION)

BY PROPORTION FOR EASTINGS AND CENTER LINE OF THE COUNTY ROAD FOR NORTHINGS, I SET 1" X 30" IRON PIPE WITH 2 3/8" BRASS CAP STAMPED AS ABOVE, 4" BELOW THE SURFACE OF A GRAVEL ROAD.

NEW ACCESSORIES FROM WHICH

AN ALUMINUM TAG, #951, ON A POWER POLE LIES S 69°.24'40" W, 43.56 FEET.
A 5/8" X 30" REBAR WITH PLASTIC CAP #951, LIES S 64°.35'31" W, 43.27 FEET.
AN ALUMINUM TAG, #951, ON A POWER POLE, LIES N 46°.39'40" W, 54.32 FEET.
A 5/8" X 30" REBAR WITH A 2" ALUMINUM CAP #951, LIES N 00°.02'10" E, 137.00 FEET.

LOCATION AND COMMENTS

AT INTERSECTION OF OLD STAGE GULCH ROAD AND LARGE POWER LINE.

COMPASS DEC.

FIRM/AGENCY
EDWARDS SURVEYING
P.O. BOX 763
HERMISTON, OREGON 97838
97838

PARTY CHIEF
D. EDWARDS

NOTES

WITNESS
RICK SMITH

SURVEYOR'S SEAL

RECEIVED BY
Umatilla County Surveyor
Date 10-98
Rec'd By KK
No. 98-213-C

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951
RENEWS 12/31/99