

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/16/05

CORNER DESIGNATION: 4N30J21, the Northeast Corner of Section 14.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was originally established by Dolphus S. Payne under Contract No. 100, dated August 1, 1861. Original notes state: Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 11, 12, 13, 14.

**MONUMENT AND ACCESSORIES FOUND:**

Found and accepted a fence corner with fences running North, South, East, and West as best remaining evidence of original corner.

**MONUMENT MARKING DETAIL:**

T4N R30E  
S11|S12  
S14|S13  
2005  
PLS 1106

**MONUMENT SET:**

At a point 4" South of railroad tie fence corner post, set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, 26" in the ground. Monument is marked as shown in Monument Marking Detail.

**New Accessories:**

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: North 00° East a distance of 58.6 feet.  
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: North 90° East a distance of 52.6 feet.  
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: South 00° West a distance of 48.9 feet.  
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: North 87° West a distance of 23.1 feet. This accessory is at a gate post on west side of gate.

Attached "witness" sign to railroad tie fence corner post 4" North of monument. Wired bearing object signs to rebar accessories.

**LOCATION AND COMMENTS:**

Located at fence intersection on East side of North-South field road.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N30J21

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-06*