

CORNER RESTORATION FORM

Township 3N & 4N Range 30E Section 4 & 33 County UMATILLA

State OREGON Date 5-6-2015 Number A-11

Corner Designation : 1/4 SECTION 4 & 33

- Condition Report Only
- Not Found
- Renewed
- Surveyed In
- Referenced


Previous Renewals ORIGINAL SOURCE OF CORNER

UNDER GLO CONTRACT #84 BY N. GATES DATED
JULY 22, 1859 SET POST

Accessories Found:
NONE

MONUMENT DETAIL

Found Set



BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE COORDINATES NORTH ZONE:

NORTHING: 772768.929
 EASTING: 8567333.253

Monument & Accessories Set (Procedure and Description)

- SET 2 1/2" BRASS CAP ON 1 1/4"x30" PIPE 2' BELOW GRADE IN FIELD.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE IN FENCE LINE, BEARING OBJECT SIGN ON RAILROAD TIE POST, N4°13'W 305.64'.
- SET 5/8" REBAR & CAP PLS 61420 1.5' BELOW GRADE IN FIELD, S67°22'E 14.52'.
- SET 5/8" REBAR & CAP PLS 61420 1.5' BELOW GRADE IN FIELD, S19°16'W 18.77'.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE IN FENCE LINE, BEARING OBJECT SIGN ON RAILROAD TIE POST, S49°37'W 292.94'.

<p>Sketch of Monument, Accessories and General Area</p> <p>SET 5/8" REBAR & CAP PLS 61420 AT GRADE IN FENCE LINE, BEARING OBJECT SIGN ON RAILROAD TIE POST</p> <p>FIELD</p> <p>20'±</p> <p>STAGE GULCH ROAD (GRAVEL)</p> <p>FIELD</p> <p>SET 5/8" REBAR & CAP PLS 61420 AT GRADE IN FENCE LINE, BEARING OBJECT SIGN ON RAILROAD TIE POST</p> <p>S49°37'W 292.94'</p> <p>N4°13'W 305.64'</p> <p>SET 2 1/2" BRASS CAP ON 1 1/4"x30" PIPE 2' BELOW GRADE IN FIELD</p> <p>S67°22'E 14.52'</p> <p>SET 5/8" REBAR & CAP PLS 61420 1.5' BELOW GRADE</p> <p>S19°16'W 18.77'</p> <p>SET 5/8" REBAR & CAP PLS 61420 1.5' BELOW GRADE</p>	<div style="border: 1px solid black; padding: 5px; text-align: center;"> <p>REGISTERED PROFESSIONAL LAND SURVEYOR</p> <p><i>Lance Clark King</i></p> <p>OREGON MAY 10, 2011 LANCE CLARK KING 61420</p> <p>RENEWS: 6/30/2015 7</p> <p>Agency: CK3, LLC 945 W. ORCHARD HERMISTON OREGON 97838 OFFICE: 541-567-2345 FAX: 541-567-2305 WEB: CK3LLC.NET Field Book# 0-289</p> <p>COUNTY SURVEYOR RECORDING INFO</p> <p>Received <i>May Robert</i></p> <p>Filed <u>6/12/2015</u></p> <p>Survey No. <u>15-050-C</u></p> <p>Drawing No. <u>C-853</u></p> <p>Index No. <u>A-11</u></p> </div>
---	--