OREGON CO NER RESTORATION FORM Section 05, 06 Township 4N Range 31E County Umatilla 05-08-2006 Date: Corner Designation: 4N31E A5 Condition Report Only Not Found Remonumented Unrecorded Surveyed In Previous Renewals / Surveys, etc. Referenced Out 08-1865 W.Odell/Lewis STD PARALLEL "Set post Standard corner for Sec (110) 31 & 32. Drove charred Stake and Raised Mound with pits as per instructions." 01-1867 W.Odell GLO Subdv (114) "Intersected 1st Standard parallel North 77 links West of Post Standard corner for sections 31 & 32 T5N R31E, At point of intersection set Closing corner for sections 5 + 6 drove charred stake dug pits, and raised mound as per instructions." ---SUBDIVISION OF T4NR31E--pits, and raised mound as per instructions. " ---SUBDIVISION OF T4NR31E--10-1907 J.Kimbrell (#256) Book 2, page 62 "Set Stone 16x8x6 inches West of this Standard 70 lks dist for cc to sec 5&6. \star × Note: T5NR31EZ5 corner referred by the following surveys is found to be the closing corner for T4NR31EA5. (see filed corner certification) \star \star 05-1974 D.Krumbein (I-25-B) "FND FENCE COR SET BRASS CAP" 06-1974 D.Krumbein (I-24-B) "FND FENCE COR SET BRASS CAP" 06-1974 D.Krumbein (I-167-B) "FND FENCE COR SET BRASS CAP" 05-1980 W.Kimmel BLM (83-195-B) "...monumented with an iron post, 2 ins. diam., firmly set, projecting 6 ins. above ground, with brass cap mkd." 05-2006 D.Haddock (06-263-C) "Found Brass cap". Monument and Accessories Found: (condition and source) Searched for and did not find stone or fence post. Found 2-3/8 dia Brass Capped monument on a 2" dia Iron pipe 2 ins. above ground and leaning 15° South.*10-2006 Stamped cap correction* th RM 4 DIAGRAM | 5' Steel T-Post Co SURVEYOR 5 ft steel T-Post with a Umatilla County Survey Springs T5NR31E sign. seci sec 31 30 South Cold Springs RM 3 Highway centerline 6 5 出 S75 °48 'E 197 ighway sec sec 5/8"dia. x 24" long 287 . Oft T4NR31E Iron Rebar with a RM 2 1.3"dia.Red Plastic cap. RLS 625 X. ← Fnd 2-3/8"dia. Brass cap on a 2.00"OD Galvanized S89 *39 'E 256.1ft pipe monument. N88 *29 2.5ft MONUMENT(S) AND ACCESSORIES SET (Procedures and Description) RM Set a 5' T-Post East of RM1 with a Bearing Object sign at the base. (1) Set a 5 ft steel T-Post with a Umatilla County Survey Marker sign facing SouthWest toward South Cold Springs highway. (11-2006: Stamped BC w/ center mark, cc and line, and corrected sec no.) REFERENCES SET: Set four (5/8" dia x 24" long Iron rebar with a 1.3" dia. Red Plastic cap) to the bearings and distances from monument shown above in the sketch. Made GPS tie to TRI Stations LAURILA RESET RB 1379 and Oregon State Plane Coord. - North Zone Northing 804539.15 WALLS RB 1396 8590701.61 Easting 45 *51 ' 48 . 026317 "N 118 *58 ' 28 . 393908 "W Latitude Ortho Height 1166.29 Longitude Ellipsoidal Height 1028.40 NAD 83 (1991) Compass Declination Location and Comments 18 °E Surveyors Seal Proceed from the Jct of Hwy 37 and South Cold Sprnigs Highway 2.00 miles South East on South Cold Springs Highway. Corner is North of the Highway 275 feet up the plowed field. Mile-post 23-1/4. REGISTERED PROFESSIONAL LAND SURVEYOR RECEIVED BY: David L. Haddock Firm / Agency OREGON Date: 05-06 JULY 12, 1968 Haddock Surveying P. O. Box 1574 Pendleton, OR 97801 (541) 276-2174 DAVID L RENEWS 6-30-07