## OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/20/05

CORNER DESIGNATION: 4N31J-03, The North Quarter Corner of Section 18.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Wm. H. Odell, under Contract No. 114, Dated July 2 1866. Record states: Set 1/4 Sec. post Cor.; drove charred stake, dug pits & raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. There is a old North South fence through corner area.

## MONUMENT MARKING DETAIL:

**T4N R31E** 

1 S7

4 S18 2005

2003

PLS 1106

MONUMENT SET: Holding old North-South fence line for departure, I re-establish this corner position at it's intersection with a line between the Northeast and Northwest corners of Section 18. At re-established corner position, set a 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe, 30" in the ground, marked as shown in Monument Marking Detail.

## New accessories:

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears North, 43.1 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears North, 19.9 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears South, 9.6 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears South, 32.5 feet.

Nailed a "witness" sign to wood fence post 10 feet South of corner. Rebar accessories have bearing object signs attached. Rebar accessories are in old North-South fence line.

LOCATION AND COMMENTS: Corner is in North-South fence about 150 feet South of draw with road in it.

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\4N31J03

PROFESSIONAL LAND SURVEYOR

> OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

renews 6-30-06

RECEIVED BY

Umatilla County Surveyor

Date 6-05

Rec'd By