

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 10/05/18.

CORNER DESIGNATION: J-5, The Northeast corner of Section 18, Township 4 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Odell and Lewis, Deputy Surveyors, under Contract No. 110, dated February 7, 1865. Notes state:

Set post corner for Secs. 7, 8, 17 & 18. Drove charred stake. Dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner at the intersection of an old fence line running East-West with a field berm extending North.

MONUMENT MARKING DETAIL:

T4N R33E
S7 | S8

S18 | S17
2018
PLS 1106

MONUMENT SET: Set a 2 3/8" brass cap on 1 1/4 by 30" galvanized iron pipe 30 inches in the ground. Cap marked as shown in Monument Marking Detail.

New accessories:

- A 5/8" by 24" rebar with red plastic cap bears East, 14.1'.
- A 5/8" by 24" rebar with red plastic cap bears East, 26.0'.
- A 5/8" by 24" rebar with red plastic cap bears S 89° W, 13.7'.
- A 5/8" by 24" rebar with red plastic cap bears S 89° W, 25.4'.

Red plastic caps are marked "ORPLS 1106 WAPLS 17372". All rebar accessories have "bearing object" signs wired to them. Set steel fence post 1.5' West of corner and attached "Witness" sign.


LOCATION AND COMMENTS: Corner is located at the intersection of an old East-West fence line with a field berm extending North.

FIRM: Wells Surveying

P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

IAN33J-5



renews 6-30-20

RECEIVED BY
Umatilla County Surveyor
Date: 10/11/2018
Field By: TMA
NO: 18-087-R