

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 10/06/08

CORNER DESIGNATION: N-21, The Northwest corner of Section 24, Township 4 North, Range 34 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by William H. Odell, Deputy Surveyor, under contract NO. 114 dated July 2, 1866. Notes state: Set post corner for sections 13, 14, 23, and 24. Drove charred stake, dug pits and raised mound as per instructions.

Also see Umatilla County Record Survey No. 08-084-C.

MONUMENT AND ACCESSORIES FOUND: None. Held a railroad tie fence post with field berms extending North, East and West, as the best remaining evidence of the original corner.

MONUMENT MARKING DETAIL:

T4N R34E
S14|S13
S23|S24
2008
PLS 1106

MONUMENT SET: At a point 0.6 feet South of the railroad tie fence post set a 2 3/8" dia. Brass cap on a 1 1/4"x30" galvanized iron pipe, with cap flush with the ground. Cap is marked as shown in "Monument Marking Detail".

New accessories:

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" 2" above ground level bears North 21° East, 24.0 feet.

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" 2" above ground level bears North 83° East, 27.2 feet.

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" 2" above ground level bears North 83° West, 17.3 feet.

The brass cap marking the North One-Quarter Corner of Section 24 bears South 89°08'31" East, 2637.46 feet.

Attached bearing object signs to all iron rebar accessories. Attached witness sign, facing East, to the railroad tie fence corner post North of corner monument.

LOCATION AND COMMENTS: Corner is 0.6 feet South of a railroad tie fence corner post with field berms extending North, East, and West. The iron rebar accessories are located in the unfarmed scab area where three farmed fields join.


FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N34N21



William R. Wells



Renews 6-30-16

RECEIVED BY
Umatilla County Surveyor
Date 10-08
Rec'd by RK
No. 08-140-R