

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/02/01

CORNER DESIGNATION: X-9, the West 1/4 Corner of Section 33, T4N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by William H. Odell under Contract No. 114, dated July 2, 1866. Original notes state: Set post for 1/4 Sec.; drove charred stake, dug pits and raised mounds as per instructions.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T4N R34E
1/4
S32|S33
2001
PLS 1106

MONUMENT SET:

At position determined by survey, set a 2 1/2 inch brass cap on 1 1/4 inch x 30 inch galvanized iron pipe with cap buried 20 inches below ground in farmed field stamped as shown on "Monument Marking Detail".

New Accessories:

- A silver Deep-1 Magnet buried 18 inches in the ground bears N 50° E, 38.8 feet.
 - A purple Deep-1 Magnet buried 18 inches in the ground bears S 47 1/2° E, 38.9 feet.
 - A blue Deep-1 Magnet buried 18 inches in the ground bears S 50° W, 39.1 feet.
 - An orange Deep-1 Magnet buried 18 inches in the ground bears N 52 1/2° W, 40.1 feet.
- Buried bearing object tags alongside all magnet accessories.

LOCATION AND COMMENTS:

Corner is located approximately 6 feet south of an East-West field berm.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Kevin Snively
4N34X9

Surveyor's Seal



renews 6-30-02

RECEIVED BY

Umatilla County Surveyor
Date 4-01
Rec'd By KR
No. 01-52-C