

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/13/01

CORNER DESIGNATION: A-13, Northwest Corner of Section 3, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, Under Contract No. 110, dated Feb. 7, 1865. Record states: Set post Closing Cor. for Secs. 3 & 4, drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
S33
S4 | S3
CC
T4N R35E
2001
PLS 1106

MONUMENT SET:

At point determined by single proportionate measurement as shown on accompanying Record of Survey, set a 2 1/2" brass cap on a 1" X 30" galvanized iron pipe, with cap buried 12" below road surface, stamped as shown in "Monument Marking Detail".

From which:

A brass washer stamped "PLS 1106", 1.0 feet above ground level, in a sawn off guard pole by phone box, bears N 86° E, 98.5 feet.

A purple deep-1 magnet, 18" below ground surface, bears S 56° E, 35.2 feet.

A blue deep-1 magnet, 18" below ground surface, bears S 50 1/2° W, 34.3 feet.

An orange deep-1 magnet, 18" below ground surface, bears N 43° W, 32.9 feet.

Buried bearing object tags with deep 1 magnets.

Attached bearing object tag to sawn off pole by phone box and also attached "witness" sign.

LOCATION AND COMMENTS: Corner is located at the visual centerline of Watts Road.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD83(91), International Feet:

N: 806474.28

E: 8727993.75

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

4N35A13

renews 6-30-02

02-12-C