

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/03/02

CORNER DESIGNATION: A-3, the North 1/4 Corner of Section 6 only.

PREVIOUS RENEWALS/SURVEYS ETC.: None. Corner was not originally established.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E

1/4 S6
T4N R35E
2001
PLS 1106

MONUMENT SET:

At a point determined by survey as shown on the accompanying Record of Survey, set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe, with cap buried 20" below ground, marked as shown in monument marking detail.

From which:

- A silver deep-1 magnet, buried 20" in ground, bears N 33° E, 33.7 feet.
 - A purple deep-1 magnet, buried 20" in ground, bears S 35° E, 43.5 feet.
 - A blue deep-1 magnet, buried 20" in ground, bears S 38 1/2° W, 47.6 feet.
 - An orange deep-1 magnet, buried 20" in ground, bears N 52° W, 42.1 feet.
- Buried bearing object signs alongside the deep-1 magnets.

LOCATION AND COMMENTS: Corner falls in an active farmed field, between two field terraces. An opinion from BLM was required to determine the proper location for this corner. See attached BLM letter.

OREGON STATE PLANE COORDINATES, North Zone, NAD 83(91), International Feet:

N: 806268.18
E: 8714700.39

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
14N35A3

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C