

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 06/12/01

CORNER DESIGNATION: C-13, the West 1/4 Corner of Section 3, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set 1/4 Sec. Cor.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R35E  
1/4  
S4 | S3  
2001  
PLS 1106

MONUMENT SET:

At a point determined by single proportionate measurement as shown on the accompanying Record of Survey, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, with cap buried 18" below ground level, marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, 18" in the ground, bears N 47 1/2° E, 25.0 feet.
  - A purple deep-1 magnet, 18" in the ground, bears S 20° E, 39.1 feet.
  - A blue deep-1 magnet, 18" in the ground, bears S 44 1/2° W, 36.4 feet.
  - An orange deep-1 magnet, 18" in the ground, bears N 49° W, 30.2 feet.
- Buried bearing object signs alongside deep-1 magnets.

LOCATION AND COMMENTS: Corner falls in a farmed field.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83(91), International Feet:

N: 804813.05  
E: 8728011.58

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
W4N35C13

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

02-12-C