

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/11/01

CORNER DESIGNATION: E-13, Northwest Corner of Section 10, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for Secs. 3, 4, 9 & 10; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R35E
S4 | S3
S9 | S10
2001
PLS 1106

MONUMENT SET:

Re-established corner position by double proportionate measure between adjacent controlling corners as shown on accompanying Record of Survey and set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, with cap buried 16" below ground surface, marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 16" in ground, bears N 43 1/2° E, 34.7 feet.
 - A purple deep-1 magnet, buried 16" in ground, bears S 50° E, 28.2 feet.
 - A blue deep-1 magnet, buried 16" in ground, bears S 45° W, 26.5 feet.
 - An orange deep-1 magnet, buried 16" in ground, bears N 34° W, 31.3 feet.
- Buried bearing object signs alongside all deep-1 magnets.

LOCATION AND COMMENTS: Corner located in farmed field.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83-(91), International Feet:

N: 802164.63
E: 8728039.99

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla

W4N35E13

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-0