

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 06/08/01

CORNER DESIGNATION: E-17, Northwest Corner of Section 11, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for Secs. 2, 3, 10 & 11, on level; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Calls from original notes to topography near corner point appear to be false or extremely inaccurate.

**MONUMENT MARKING DETAIL:**

T4N R35E  
S3 | S2  
S10 | S11  
2001  
PLS 1106

**MONUMENT SET:**

Re-established corner position by double proportion measure between adjacent corners or features, as shown an accompanying Record of Survey and set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, with cap buried 16" below ground, stamped as shown in "Monument Marking Detail".

From which:

- A main line irrigation riser head at a corner where 3 fields come together bears N 89° E, 167.5 feet.
- A purple deep-1 magnet, buried 16" below ground, bears S 38 1/2° E, 37.9 feet.
- A blue deep-1 magnet, buried 16" below ground, bears S 48 1/2° W, 40.9 feet.
- An orange deep-1 magnet, buried 16" below ground, bears N 38° W, 48.0 feet.
- Buried bearing object signs alongside deep-1 magnets.
- No sign on irrigation riser head.

LOCATION AND COMMENTS: Corner is located about 6 feet South of South edge of a East/West field road.

OREGON STATE PLANE CO-ORDINATES, Oregon North, NAD 83(91), International Feet:

N: 802108.18  
E: 8733328.55

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla

4N35E17

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

*02-12-C*