

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/04/02

CORNER DESIGNATION: E-7, the North 1/4 Corner of Section 8.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally set by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T4N R35E
S5
1/4-----
S8
2002
PLS 1106

MONUMENT SET:

At the intersection of a line between the reestablished Northeast and Northwest corners of Section 8 and an ancient field berm extending North and South, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe with cap buried 20" below ground, marked as shown in monument marking detail.

From which:

- A silver deep-1 magnet, 20" in ground, N 47 1/2° E, 33.9 feet.
 - A purple deep-1 magnet, 20" in ground, S 46° E, 35.1 feet.
 - A blue deep-1 magnet, 20" in ground, S 35° W, 30.7 feet.
 - An orange deep-1 magnet, 20" in ground, N 37° W, 26.8 feet.
- Buried bearing object signs alongside the deep-1 magnets.

LOCATION AND COMMENTS:

Corner is located in a North-South field berm approximately 1/2 mile North of County Road.

OREGON STATE PLANE COORDINATES, North Zone, NAD 83(91), International Feet:

N: 802113.74
E: 8720070.66

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla
V4N35E7

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renew 6-30-02

02-12-C