

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/27/00

CORNER DESIGNATION: J-11, North 1/4 Corner of Section 16, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated 2 July, 1866. The original notes state: Set post Cor. For 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by K.E.L. in 1983, Survey No. 83-76-C. Notes state: Set B.C. at the intersection centerline point of a county road running East-West with a county road running South and fence line running North.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 1/2" brass cap on a 1 1/4" galvanized iron pipe. Top of is cap 1.0' below road surface. Monument marked as shown in "Monument Marking Detail".

MONUMENT MARKING DETAIL:

T4N R35E
1/4 S9
S16
1983
County Surveyor

NEW ACCESSORIES TO EXISTING MONUMENT:

A brass washer stamped "PLS 1106", 1.0 feet above ground in South face of railroad tie bears N 35° E, 15.5 feet.

A brass washer stamped "PLS 1106", 1.0 feet above ground in North face of Pacific Power and Light Pole #164903 bears S 70° E, 59.3 feet.

A brass washer stamped "PLS 1106", 1.0 feet above ground in North face of Pacific Power and Light pole #164902 bears S 10° W, 90.8 feet.

A brass washer stamped "PLS 1106" 1.0 feet above ground in North face of Pacific Power and Light pole #164901 bears S 81° W, 85.1 feet.

Attached bearing object signs to all new accessories.

Attached "witness" sign to railroad tie 13 feet North of corner monument.

LOCATION AND COMMENTS: Located at intersection of Schrimpf and Johnson Roads.

OREGON STATE PLANE COORDINATES, Oregon North, NAD 83(91), International Feet:

N = 796806.53
E = 8725580.33

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 20° East

Witnesses: Jason Wells
Kevin Snively
4N35J11

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-02