

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 06/07/01

CORNER DESIGNATION: J-17, Northwest Corner of Section 14, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell under Contract No. 114, dated July 2nd, 1866. Record state: Set post Cor. for Secs. 10, 11, 14 & 15; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R35E  
S10 | S11  
S15 | S14  
2001  
PLS 1106

MONUMENT SET:

To re-establish this corner, I held a East-West field line at the corner position for latitude and proportioned record departure between the re-established or recovered North 1/4 Corners of Sections 14 and 15. At position determined by survey, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe with cap buried 16" below farmed field, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, 18" below ground level, bears N 45° E, 26.4 feet
  - A purple deep-1 magnet, 18" below ground level, bears S 38° E, 26.9 feet.
  - A blue deep-1 magnet, 18" below ground level, bears S 46 1/2° W, 30.5 feet.
  - An orange deep-1 magnet, 18" below ground level, bears N 43° W, 27.0 feet.
- Buried object signs alongside deep-1 magnets.

LOCATION AND COMMENTS: Corner falls in East-West field line.

OREGON STATE PLANE CO-ORDINATES, Oregon North, NAD 83(91), International Feet:

N: 796802.00  
E: 8733471.99

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla

V4N35J17

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renew 6-30-02*

*02-12-C*