

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/29/01

CORNER DESIGNATION: J-3, North 1/4 Corner of Section 18, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set 1/4 Sec. Cor. post; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R35E
1/4 S7
S18
2001
PLS 1106

MONUMENT SET: At position determined by single proportionate measure between the recovered Northeast Corner of Section 18 and a 2 1/2" iron pipe referred to on Survey No. S-140-C found at the West 1/16th Corner of Section 18, set a 2 1/2" aluminum cap on 2 1/2" by 30" aluminum pipe with cap buried 12 inches below ground level, stamped as shown in "Monument Marking Detail".

From which:

- A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap set 14" in the ground, bears N 61 1/2° E, 31.1 feet.
 - A purple deep-1 magnet, buried 14" in the ground, bears S 53° E, 32.5 feet.
 - A blue deep-1 magnet, buried 14" in the ground, bears S 44° W, 23.6 feet.
 - A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap set 14" in the ground, bears N 44° W, 22.9 feet.
- Buried bearing object signs alongside all new accessories.

LOCATION AND COMMENTS: Corner is in an East-West field berm.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83(91), International Feet:
N: 796399.60
E: 8714942.54

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
V4N35J3

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C