

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 12/31/01

CORNER DESIGNATION: J-9, Northwest Corner of Section 16, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for Secs. 7, 8, 17 & 18; drove charred stake, dug pits and raised mound as per instructions. Corner recovered by J. C. Arnold, County Surveyor, on Umatilla County Survey No. 44, recorded at Book 1, Page 221. Record states: Int. N.S. line 60 3/4 ft. N. of cor. To secs. 8-9-16-17, which is a basalt sonte 12x10x5 ins., unmarked, 8 ins. In ground, by a fence Post in angle of fences E & S. - I find remnants of decayed stakes, fir and cottonwood, under the stone. I therefore mark the stone, 4 notches S & E. and replace it. Note: There is also a "long" tie to this corner from the railroad maps of the Oregon-Washington Railroad and Navigation Company Maps. This railroad tie was used by Bartelson to calculate the corner location in Partition Plat No. 1995-29.

MONUMENT AND ACCESSORIES FOUND:

None. The corner area has been extensively farmed. I reestablished this corner at the intersection of field lines North-South and East, the field lines being the best evidence of the original corner location. Reestablished corner position fits well with record dimensions of Surveys (R4) and (R5) identified on the accompanying Record of Survey.

MONUMENT MARKING DETAIL:

T4N R35E
S8 | S9
S17|S16
2001
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on 1 1/2" by 30" galvanized iron pipe, with cap buried 20" below ground level, marked as shown on "Monument Marking Detail", from which:

- A silver "deep-1" magnet, buried 20" in the ground, bears N 51 1/2° E, 30.1 feet.
- The top center of a irrigation pipe riser bears S 02° E, 34.8 feet.
- A blue "deep-1" magnet, buried 20" in the ground, bears S 55° W, 39.0 feet.
- A orange "deep-1" magnet, buried 20" in the ground, bears N 60 1/2° W, 33.4 feet.

Buried bearing object signs alongside "deep-1" magnets.

LOCATION AND COMMENTS:

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83 (91), International Feet:

N: 796713.82
E: 8722933.60

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

V4N35J9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-c