

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/25/01

CORNER DESIGNATION: L-13, West 1/4 Corner of Section 15, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner recovered by J.C. Arnold in Umatilla County Survey Book 1 Page 221, dated 1889. Record states: Found several ends of decayed stakes varying in character and size, but find no charcoal. Set a basalt stone 13 x 9 x 7 ins., 20 ins. In ground for 1/4 sec. cor., mkd. 1/4 on W. Deposit charcoal and place top of original post in mound over stone, on N.E. slope of hill.

## MONUMENT AND ACCESSORIES FOUND:

### MONUMENT MARKING DETAIL:

T4N R35E  
1/4  
16 | 15  
2001  
PLS 1106

### MONUMENT SET:

At position determined by single proportionate measurement between the recovered or re-established Northwest and Southwest Corners of Section 15, using J.C. Arnold's Record, set a 2 1/2" brass cap on 1" by 30" galvanized iron pipe with cap 1" below existing paved road. Brass cap stamped as shown in "Monument Marking Detail".

#### From which:

A brass washer stamped "PLS 1106", 1.0 feet above ground level, in a power pole, bears N 80° E, 92.3 feet.

The center of a "20 MPH" curve sign pole, bears S 81° E, 126.3 feet.

A 5/8" x 30" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", 1" above ground surface, bears S 76° W, 46.4 feet.

An orange deep-1 magnet, buried 18" below ground surface, in field, bears N 17° W, 29.0 feet.

Set steel fence post near 5/8" rebar accessory and attached "witness" sign. post. Attached bearing object signs to power pole and 5/8" iron rebar accessories. Buried bearing object sign alongside the deep-1 magnet.

LOCATION AND COMMENTS: Monument set 6 feet North of South edge of paved road running East/West, 1 inch below road surface.

OREGON STATE PLANE CO-ORDINATES, Oregon North, NAD 83(91), International Feet:

N: 794180.94

E: 8728299.17

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla

14N35L13

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

*02-12-e*