

OREGON CORNER RESTORATION FORM

CORNER N-17

Section 23 Township 4N Range 35E

CROSS REFERENCE:

County UMATILLA Date MARCH 8, 1991

MAP 91-018-B

CORNER DESIGNATION

515 | 514
522 | 523

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. ORIG: WM ODELL, CN 114, 1866" POST, CHARRED STAKE, PITS AND MOUND. MAP Q-719-A DESIGNATES CORNER AS "I.P.". MAP B3-76-C REPORTS RE-ESTABLISHMENT FROM CEMETERY WELL.

Monument(s) & Accessories Found: (Condition and Source)

FOUND 1/2 X 1/2" IRON BAR WITH TOP AT A DEPTH OF 2 1/2' AND A VERY OLD BUT WELL PRESERVED SURVEY STAKE. THE IRON BAR IS 2' LONG AND IS THE "I.P." REFERENCED IN SURVEY MAP NO. Q-719-A, THIS FACT BEING VERIFIED BY TIES TO THE WESTON CEMETERY WELL. I FIND NO EVIDENCE OF REMONUMENTATION AS REPORTED ON MAP B3-76-C. CORNER FALLS IN ACTIVE GRAIN FIELD.

Monument Detail

SET 2 1/2" BRASS CAP ON 1/4 X 30" GALV. IRON PIPE WITH TOP OF CAP BURIED 2' BELOW GROUND SURFACE. SET STEEL FENCE POST IN EDGE OF ROAD SOUTH-167 FEET FROM CORNER.

Sketch

CAP MARKED:
T4N R35E

515 | 514
522 | 523
1991
PLS1106

Monument Set (Procedures and Description)

AT THE POSITION OF THE FOUND IRON BAR, SET A 2 1/2" BRASS CAP ON 1/4" X 30" GALV. IRON PIPE AS DESCRIBED ABOVE. PLACED IRON BAR ALONGSIDE OF NEW MONUMENT.

NOTE REGARDING ACCESSORIES; SINCE CORNER FALLS SO NEAR THE CEMETERY, BEARING OBJECT SIGNS WERE NOT PLACED EXCEPT ON

NEW ACCESSORIES THE BRIDGE EAST OF CORNER.

- ① THE 2 1/2" PIPE AT THE CHAIN LINK FENCE CORNER AT THE NE CORNER OF THE WESTON CEMETERY BEARS S61 1/2° W - 34.4'
- ② A CONCRETE NAIL WITH BRASS WASHER STAMPED "PLS 1106" NAILED TO BRIDGE DECK AT THE N.W. CORNER OF BRIDGE ON HALE CREEK BEARS N 88° E - 422.7'
- ③ THE N.E. CORNER OF THE 20' X 15' BASE OF THE SADIE H. HARRIS GRAVESTONE BEARS S 60° W - 100.0'
- ④ THE BOTTOM NORTH CORNER OF THE "A" ON NAME "HARTMAN" ON THE EAST FACE OF THE HARTMAN FAMILY MEMORIAL STONE BEARS S 46 1/2° W - 82.3'

Location & Comments

CORNER LOCATED IN ACTIVE Compass Declination 18°
GRAIN FIELD N 61 1/2° E - 34.4' Firm/Agency WILLIAM R.
FROM FENCE CORNER AT WELLS, PLS
THE NE. CORNER OF THE Address P.O. Box 1696
WESTON CEMETERY PENDLETON, OR

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

RECEIVED BY

Umatilla County Surveyor

Date 3-91

Rec'd by KA

No. 91-17-C

Party Chief BILL WELLS

Notes

Witness BILL QUAMPTS