

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/06/97

CORNER DESIGNATION: N-7, The North Quarter Corner of Section 20, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

This corner was recovered and remonumented with a 21 x 14 x 7 inch stone in the center of a lane, by J.C. Arnold, County Surveyor, in Survey No. 58, in December, 1893.

MONUMENT AND ACCESSORIES FOUND: None. This corner was re-established by single proportion measurement between the Northwest and Northeast corners of Section 20 using distance record from County Survey No. 58.

MONUMENT MARKING DETAIL:

T4N R35E
1 S17
4 S20
1997
PLS 1106

MONUMENT SET:

A 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, 18" below surface of cultivated field, marked as shown in monument marking detail.

New Accessories:

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 48° E, 26.3 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 54° E, 24.0 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 42° W, 20.4 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 40° W, 20.8 feet.

All iron rods have bearing object signs attached and are 18" below field surface.

Steel fence post approximately 75 feet North of monument, in field line, with witness sign attached.

LOCATION & COMMENTS: This corner falls in cultivated field about 75 feet South of an established East-West field line. I find no record evidence which would justify re-establishing this corner in the field line.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells

OREGON NORTH STATE PLANE CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 791299.57
E: 8720490.03

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

97-141-C