

OREGON CORNER REFORMATION FORM

COUNTY: Umatilla DATE: 06/27/97

CORNER DESIGNATION: P-5, The East Quarter Corner of Section 19, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner was re-established by John Kimbrell, County Surveyor, during County Survey No. 73, recorded in Record of Private Surveys Book 1, Pages 305-318, dated April 1895. Kimbrell set a 17 x 9 x 16 inch stone.

MONUMENT AND ACCESSORIES FOUND: None. Re-established corner position at the intersection of the line between the Northwest and Southwest corners of Section 20 and the Easterly projection of the East-West centerline of Section 19 as shown and identified on Umatilla County Surveys K-73-B and M-12-B.

MONUMENT MARKING DETAIL:

T4N R35E

1

4

S19 | S20

1997

PLS 1106

Note: A rock disk was used because road surface is concrete, 4 inches below asphalt surface.

MONUMENT SET:

Set a 2 1/2" brass rock disk 4" below existing asphalt road, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 53° E, 39.3 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 55° E, 40.0 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 43° W, 32.7 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 60° W, 33.1 feet.

All iron rods have bearing object tags attached and a steel fence post nearby with witness sign attached.

LOCATION & COMMENTS: Corner is located in the approximate centerline of Banister Road, Highway 11 is approximately 800.00 feet East. Pacific Power and Light pole #199402 is 27.5 feet South of monument location.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: John Linder
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 788475.80

E: 8717742.14

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Renews 6-30-98

97-141-C