

OREGON CONFIRMATION FORM

COUNTY: Umatilla DATE: 06/17/97

CORNER DESIGNATION: P-9, The East Quarter Corner of Section 20, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. This corner was reported as established on Survey No. 83-156-C.

MONUMENT AND ACCESSORIES FOUND: None. After extensive search and surveying into the corner area, the brass cap monument reported on Survey No. 83-156-C was declared lost. The corner position was re-established using the record angle from Survey No. 83-153-C at the Southwest corner of Section 21, using the South Quarter corner of Section 21 as a backsight. The record distance from the Southwest corner of Section 21 was applied to calculate the corner position.

MONUMENT MARKING DETAIL:

T4N R35E
1
4
S20 | S21
1997
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 6 inches below surface of paved road, monument marked as shown in monument marking detail.

A brass washer stamped "PLS 1106" nailed to a telephone pole marked "RPR2", bears N 75° E, 171.0 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 50° E, 29.3 feet.

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light pole #209502, bears S 23° W, 26.4 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 51° W, 34.9 feet.

Attached bearing object signs to all iron rods.

Iron rod in Southeast quadrant has a steel fence post nearby with a witness sign attached.

Steel fence post 25 feet South of monument with witness sign attached.

Telephone pole and Power pole have bearing object and witness signs attached.

LOCATION & COMMENTS: Monument located in the South lane of the road heading between Athena and Weston, approximately 600 yards East of Natural Gas Station Building.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells


OREGON NORTH STATE PLANE CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 788570.13

E: 8722901.43



Willie R. Wells



Renews 6-30-98

97-141-C