

OREGON CORNER REFORMATION FORM

COUNTY: Umatilla DATE: 03/05/97

CORNER DESIGNATION: R-11, The North Quarter Corner of Section 28, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

Corner re-established by PLS 933, Umatilla County Survey Record No. 83-156-C. Notes state: K.E.L. set B.C. at computed location by single proportion between the Section corners East and West.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on galvanized iron pipe 0.7 feet below ground surface.

MONUMENT MARKING DETAIL:

Umatilla County
T4N R35E
1 S21
4 S28
1983
PLS 933
Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 50° E, 22.5 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 35° E, 28.7 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 70° W, 30.2 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 40° W, 24.2 feet.

All iron rods are 1.8 feet below the surface with bearing object signs attached.

LOCATION & COMMENTS: Corner is 121.5 feet North of Schrimpf Road centerline and 125.5 feet East of unimproved North-South road.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:
N: 786075.23
E: 8725744.14

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98