

OREGON CORNER RE ORATION FORM

COUNTY: Umatilla DATE: 03/04/97

CORNER DESIGNATION: R-17, The Northwest Corner of Section 26, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for Secs. 22, 23, 26 & 27; drove charred stake, dug pits and raised mound as per instructions.

Corner re-established by PLS 933, Umatilla County Survey Record No. 83-156-C. Notes state: K.E.L. set B.C. at intersection of East-West fence line and center of county road running North-South, set steel fence post with survey marker sign 2.0' West and set B.O. sign.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on galvanized iron pipe 0.2 feet below ground surface. Steel fence post with witness sign 1.0 feet North of brass cap. Bearing object sign on disturbed fence post with markings: Dist: 8.0, Dir: West.

Umatilla County  
S22 | S23  
S27 | S26  
1983  
PLS 933  
Surveyor

MONUMENT MARKING DETAIL: Existing monument.

MONUMENT SET: Existing monument.

New Accessories:

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 51° E, 16.8 feet.

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 41° E, 15.7 feet.

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 39° W, 43.7 feet.

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 18° W, 61.9 feet.

Attached bearing object signs to all iron rods.

Each iron rod has a steel fence post set nearby with witness sign attached.

LOCATION & COMMENTS: Corner is 4.5 feet East of present centerline of a unimproved road heading North-South.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively  
Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 786304.23

E: 8733853.21

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*

97-141-C