

OREGON CORNER RELOCATION FORM

COUNTY: Umatilla DATE: 03/06/97

CORNER DESIGNATION: R-7, The North Quarter Corner of Section 29, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

Corner re-monumented by PLS 933, Umatilla County Survey Record No. 83-156-C. Notes state: K.E.L. found stone with "x" under fence post and set B.C. with stone reset on the North side.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on galvanized iron pipe 0.3 feet above ground surface, 0.65 feet East from 0.6 foot diameter pipe 3.5 feet above ground surface.

MONUMENT MARKING DETAIL:

Umatilla County

T4N R35E

1 S20

4 S29

1982

PLS 933

Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 52° E, 12.8 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 39° E, 11.7 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 54° W, 11.5 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 33° W, 12.1 feet.

All iron rods are 1.5 feet below the surface with bearing object signs attached.

LOCATION & COMMENTS: Corner is in intersection of four wheatfields, with field lines running North, South, East and West.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively

Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 785859.99

E: 8720360.61

REGISTERED PROFESSIONAL LAND SURVEYOR

*Will. R. Wells*

OREGON JULY 22, 1987 WILLIAM R. WELLS 1106

*Renews 6-30-98*

97-141-C