

CORNER DESIGNATION: R-9, The Northwest Corner of Section 28, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for Secs. 20, 21, 28 & 29; drove charred stake, dug pits and raised mound as per instructions.

Corner re-established by PLS 933, Umatilla County Survey Record No. 83-156-C. Notes state: K.E.L. set B.C. on North side of 4" ductile iron sewer line used as a post in an East-West fenceline 8" in length with 4 feet above ground, no stone beneath this post.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on galvanized iron pipe 0.2 feet above ground surface, directly against a 0.6 inch diameter pipe 3.0 feet above the ground. Brass cap is on the North side of pipe. Witness sign is attached to the pipe.

MONUMENT MARKING DETAIL:

Umatilla County
T4N R35E
S20 | S21
S29 | S28
1983
PLS 933
Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 40° E, 14.6 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 57° E, 14.5 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 49° W, 13.1 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 48° W, 17.1 feet.

All iron rods are 1.5 feet below the surface with bearing object signs attached.

LOCATION & COMMENTS: Corner is in line with field lines extending East-West and South.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 785916.27

E: 8722998.42

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

97-141-R