

OREGON CORNER REFORMATION FORM

COUNTY: Umatilla DATE: 05/27/97

CORNER DESIGNATION: T-13, The East Quarter Corner of Section 28, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec.; on gentle slope to N.E.; drove charred stake, dug pits and raised mound as per instructions. Corner position was calculated as reported on Survey No. 83-156-C, but not monumented.

MONUMENT AND ACCESSORIES FOUND: Found a railroad spike at the intersection of Degraw Road and Key Cemetery Road.

MONUMENT MARKING DETAIL:

T4N R35E
 $\frac{1}{4}$
 S28 | S27
 1997
 PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 8 inches below gravel road surface, monument marked as shown in monument marking detail.

A road sign bears N 19° E, 17.7 feet.

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light pole #270401 bears S 82° E, 85.3 feet.

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light pole #270402 bears S 13° E, 83.2 feet.

A brass washer stamped "PLS 1106" nailed to a railroad tie bears S 63° W, 47.6 feet.

Attached bearing object signs to all objects.

A steel fence post with witness sign attached, 15.2 feet North of brass cap.

LOCATION & COMMENTS: Located at the intersection of DeGraw and Key Cemetery Roads.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
 Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 783568.84

E: 8728554.77

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

Renews 6-30-98

97-141-C