

OREGON COR R RE ORATION FORM

COUNTY: Umatilla DATE: 03/04/97

CORNER DESIGNATION: V-15, The North Quarter Corner of Section 34, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set 1/4 Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions.

Corner re-established by PLS 933, Umatilla County Survey No. 83-156-C. Notes state: K.E.L. set B.C. at intersection of East-West plowline and county road centerline running North-South. Set steel post with survey marker sign 25.0' West and set B.C. sign on wood post 29.4' East.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap on a galvanized iron pipe 0.8 feet below blacktop on County road in centerline of road, marked as shown below. Found monument witness sign on steel fence post 24.8 feet West of brass cap.

MONUMENT MARKING DETAIL:

Umatilla County  
1 S27  
4 S34  
1983  
PLS 933  
Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light Pole #275003, nailed 1.0 feet above ground surface, bears N 13° E, 123.7 feet.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 26° E, 49.4 feet.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 47° W, 38.8 feet.

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light Pole #275002, 1.0 feet above ground surface, bears N 11° W, 183.0 feet.

All iron rods have bearing object tags attached and steel fence posts nearby with witness signs attached.

Attached bearing object signs to Pacific Power and Light pole facing the brass cap.

LOCATION & COMMENTS: Corner is located in the centerline of McLean Road which runs North-South.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively  
Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 780961.60  
E: 8731275.40

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*