

OREGON CORNER RELOCATION FORM

COUNTY: Umatilla DATE: 06/10/97

CORNER DESIGNATION: X-17, The East Quarter Corner of Section 34, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec. on land that slopes to the N.; drove charred stake, dug pits and raised mound as per instructions. The original post for this corner was recovered by J.H. Raley, County Surveyor, in County Survey No. 17, dated May 1881.

MONUMENT AND ACCESSORIES FOUND: None. Corner was re-established at the corner of an ancient fence with wires and posts extending North-South and West.

MONUMENT MARKING DETAIL:

T4N R35E  
1  
4  
S34 | S35  
1997  
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe approximately 6" above ground, cap marked as shown in Monument Marking Detail.

Accessories:

A brass washer stamped "PLS 1106" nailed to a 12 inch diameter hawthorn tree, bears S 02° W, 14.5 feet, tree scribed "1/4 S34 BT".

A brass washer stamped "PLS 1106" nailed to a 10 inch diameter hawthorn tree, bears S 32° W, 14.3 feet, tree scribed "1/4 S34 BT".

A brass washer stamped "PLS 1106" nailed to a 10 inch diameter hawthorn tree, bears S 80° W, 15.9 feet, tree scribed "1/4 S34 BT".

A brass washer stamped "PLS 1106" nailed to a 10 inch diameter hawthorn tree, bears S 89° W, 5.2 feet, tree scribed "1/4 S34 BT".

All trees have bearing object and witness signs attached.

Set a steel fence post with witness sign attached, 30 feet East of brass cap.

LOCATION & COMMENTS: Corner located near old fence corner.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively  
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 778517.48  
E: 8734000.84

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*