

OREGON CORNER REORIENTATION FORM

COUNTY: Umatilla DATE: 05/16/97

CORNER DESIGNATION: X-5, The East Quarter Corner of Section 31, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made mound of earth for 1/4 Sec. Cor. Corner re-established by Jas. P. Currin and Jas. E. Noland, Under Special Contract, dated May 4, 1887. Notes state: Deposited charred stake, 12 ins. in the ground for 1/4 Sec. Cor., dug pits, 18 x 18 x 12 ins., N. & S. of stake, 5 1/2 ft. dist., raised mound of earth, 1 1/2 ft. high, 3 1/2 ft. base over it, and in N. pit; drove stake 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/4 S. on W. face. Wagon spindle was found for the corner by Willard Bradley, County Surveyor, in April 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by calculation with reference to County Survey No. 406, Willard Bradley, dated April 1915, after recovering the South 1/16 corner and Southeast corners of Section 31 as indicated on Bradley's Survey Plat.

MONUMENT MARKING DETAIL:

T4N R35E  
S31 ; S32  
1997  
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" galvanized iron pipe 8" below surface of unimproved road, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 18° E, 25.1 feet, steel fence post set nearby with witness sign attached.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 14° E, 25.8 feet, steel fence post set nearby with witness sign attached.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 40° W, 19.6 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 40° W, 19.8 feet.

Iron rods have bearing object tags attached.

A steel fence post with witness sign attached, 5 feet East of brass cap.

LOCATION & COMMENTS: Corner is below surface of unimproved road running North-South.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively

Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 777870.43

E: 8717990.42

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

97-141-C Renew 6-30-98