

OREGON CORNER REFORMATION FORM

COUNTY: Umatilla DATE: 05/09/97

CORNER DESIGNATION: Y-1, The South 1/16 Corner of Section 31, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: This 1/16th corner was established by Willard Bradley, County Surveyor, in April 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: Found a wagon spindle 5 feet East of North-South paved road, in line with East-West field line, and 1 foot below ground surface.

MONUMENT MARKING DETAIL:

MONUMENT SET:

New Accessories:

A railroad spike stamped "PLS 1106", bears S 21° W, 33.2 feet.
A railroad spike stamped "PLS 1106", bears N 06° W, 35.8 feet.
Railroad spikes are located approximately 1.5 feet from East edge of road in the asphalt.
Steel fence post 5 feet East of wagon spindle with witness sign attached.

LOCATION & COMMENTS: Corner is 5 feet East of East edge of Pambrun Road and in line with East-West field line.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 776440.65
E: 8712949.67

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98