

OREGON CORNER REFORMATION FORM

COUNTY: Umatilla DATE: 06/12/97

CORNER DESIGNATION: Z-11, The South Quarter Corner of Section 33, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by W. H.Odell, GLO Contract No.114, dated July 2, 1866.

Notes state:

Set post corner for 1/4 Sec., drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by single proportionate measurement between the Southwest corner of Section 32 and the Southeast corner of Section 33.

MONUMENT MARKING DETAIL:

T4N R35E
1 S33
4
T3N R35E
1997
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on 1" x 30" galvanized pipe 15" below the surface of an unimproved East-West road, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 70° E, 14.9 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 30° E, 27.9 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 43° W, 34.0 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 60° W, 18.7 feet.

All iron rods have a bearing object sign attached and a steel fence post nearby with witness sign attached.

Set steel fence post 6 feet North of monument with witness sign attached.

LOCATION & COMMENTS: Monument is located on the North side of an unimproved road, approximately 20 feet East of visible irrigation pipe.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 775517.22
E: 8726050.07

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

97-141-e