

OREGON CORNER RE-ORIENTATION FORM

COUNTY: Umatilla DATE: 06/12/97

CORNER DESIGNATION: Z-15, The South Quarter Corner of Section 34 T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by W. H. Odell, GLO Contract No.114, dated July 2, 1866.

Notes state:

Set post corner for 1/4 sec., drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Re-established corner at the centerline of a paved road heading North-South at the Westerly projection of a fenceline extending East and at the Easterly projection of an old field berm.

MONUMENT MARKING DETAIL:

T4N R35E
1 S34
4 S 3
T3N R35E
1997
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on 1" x 30" galvanized pipe 5" below the surface of a paved road heading North-South, cap marked as shown in Monument Marking Detail.

Accessories:

A road mile marker sign bears N 15° E, 111.0 feet.

A brass washer stamped "PLS 1106" nailed to a railroad tie fence post bears S 77° E, 29.2 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 48° W, 30.2 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 18° W, 57.5 feet.

Iron rods have a bearing object attached and a steel fence post nearby with witness sign attached.

Railroad tie has witness and bearing object sign attached.

Mile marker sign has a bearing object attached.

LOCATION & COMMENTS: Monument is in the middle of paved road and in line with fence extending East.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 775678.04
E: 8731349.58

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98