

OREGON COUNTY REFORMATION FORM

COUNTY: Umatilla DATE: 06/09/97

CORNER DESIGNATION: Z-3, The South Quarter Corner of Section 31, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by W. H.Odell, GLO Contract No.114, dated July 2, 1866.

Notes state: Set post corner for 1/4 Sec. Drove charred stake dug pits, and raised mound as per instructions.

Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made mound of earth for 1/4 Sec. cor.

Corner re-established by Jas. P. Currin & Jas. E. Noland, GLO Special Contract, dated May 4, 1887. Notes state: Set a post 36x3x3 ins. 12 ins. in the ground for 1/4 Sec. cor. marked 1/4 S. on N. face. Dug pits 18x18x12 ins. E. and W. of cor. 5 1/2 ft. dist. raised mound of earth 1 1/2 ft. high 3 1/2 ft. base around post. A stone was established for the corner by Willard Bradley, County Surveyor, in April 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by calculation, with reference to County Survey No. 406, by Willard Bradley, dated April 1915, after recovering the South 1/16 corner and Southeast corners of Section 31 as indicated on Bradley's Survey Plat.

MONUMENT MARKING DETAIL:

T4N R35E

1 S31

4

T3N R35E

1997

PLS 1106

See discussion of this corner on Record of Survey map filed separately.

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 8" below surface of unimproved road, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA 17372" bears N 42° E, 21.8 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 66° E, 24.2 feet.

A 5" diameter pipe 5 feet above ground bears S 04° W, 19.6 feet.

A 3" diameter pipe 4 feet above ground bears N 02° W, 21.6 feet.

Bearing object tags attached to iron rods and steel fence posts set nearby with witness signs attached.

Pipes have witness and bearing object signs attached.

LOCATION & COMMENTS: Corner is located in East-West Rainwater Road.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively

Jason Wells


OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 775172.77

E: 8715441.33



William R. Wells



Renews 6-30-98

97-141-C