

OREGON COUNTY REFORMATION FORM

COUNTY: Umatilla DATE: 05/09/97

CORNER DESIGNATION: Z-5, The Southwest Corner of Section 32, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by W. H. Odell, GLO Contract No. 114, dated July 2, 1866.

Notes state:

Set post cor. for Secs. 5, 6, 31 and 32. Drove charred stake and raised mound as per instructions.

Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made mound of earth for cor. to Secs. 5, 6, 31 & 32.

Corner re-established by Jas. P. Currin & Jas. E. Noland, GLO Special Contract, dated May 4, 1887. Notes state: Intersect S. Bdy. of Tp. 123 lks. W. of Cor. to Secs. 5 & 6, T 3 N R 35 E. and set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for closing Cor. to Secs. 31 & 32, marked C.C. T 4 N on N., R35 E S 32 on E. & S 31 on W. faces, with 5 notches on E. and 1 notch on W. edges, dug pits, 18 x 18 x 12 ins. N.E. & W. of Cor. 5 1/2 ft. dist., raised mound of earth, 2 ft. high, 4 1/2 ft. base around it.

A "large stone" was found for the corner by Willard Bradley, County Surveyor, in April 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: Found 15" diameter rock in place at intersection of East-West, North-South farm roads.

MONUMENT MARKING DETAIL:

T4N R35E See discussion of this corner on
S31 | S32 Record of Survey Map filed separately.

T3N R35E
1997
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap in center of stone, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 53° E, 36.5 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 33° E, 18.6 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 78° W, 32.6 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 38° W, 33.6 feet.

Bearing object tags attached to iron rods and steel fence posts set nearby with witness signs attached.

LOCATION & COMMENTS: Corner is located at intersection of East-West by North-South farm roads.

COMPASS DECLINATION: 18° East

Witnesses: Kelly Snively
Jason Wells

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

OREGON STATE PLANE NORTH CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 775238.12

E: 8718094.00

97-141-C