

COUNTY: Umatilla DATE: 06/12/97

CORNER DESIGNATION: Z-9, The Southwest Corner of Section 33, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by W. H. Odell, GLO Contract No. 114, dated July 2, 1866.

Notes state:

Set post corner for Sec. 4, 5, 32 & 33, drove charred stake, dug pits and raised mound as per instructions.

Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made earth mound for cor. to Secs. 4, 5, 32 & 33.

Corner re-established by Jas. P. Currin & Jas. E. Noland, GLO Special Contract, dated May 4, 1887. Notes state: Set post 48 x 4 x 4 ins. 12 ins. in the ground for cor. to Secs. 4, 5, 32 & 33. Marked T 4 N. S. 33 on N. U.R. 35, E. S. 4

S. E. T 3 N. S. 5 on S. W., S32 on N. W., with 4 notches on E., & 2 notches on W. edges, Dug pits 18 x 18 x 12 ins. in each Sec. 5 1/2 ft. dist. raised a mound of earth 2 ft. high 4 1/2 ft. base around post. Corner was re-established by John Kimbrell, County Surveyor, in survey reported in Record of Private Surveys Book 2, Page 138, dated 1909. Kimbrell set "a stone" for the corner.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by single proportionate measurement between the Southwest corner of Section 32 and the Southeast corner of Section 33.

MONUMENT MARKING DETAIL:

T4N R35E See discussion of this corner on Record of
 S32 | S33 Survey Map filed separately.

T3N R35E
 1997
 PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized pipe 12" below surface of unimproved road, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 54° E, 25.2 feet.

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light pole bears S 82° E, 174.0 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 70° W, 25.6 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 54° W, 29.0 feet.

Bearing object tags attached to iron rods. Steel fence posts set nearby with witness signs attached.

Power pole has a bearing object and witness sign attached.

Set a steel fence post 8 feet South of monument with witness sign attached.

LOCATION & COMMENTS: Corner is located on the South side of Rainwater Road approximately 187 feet West of the intersection of Wildhorse and Rainwater Roads.

97-141-0

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 775424.19
E: 8723398.04

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98