

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 10/11/19.

CORNER DESIGNATION: N-11, The North 1/4 corner of Section 21, Township 4 North, Range 36 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by William H. Odell, Deputy Surveyor, under Contract No. 114, dated July 2, 1866. Notes state:

Set post Cor. for 1/4 Sec.; drove charred stake, and raised stone mound as per instructions. In Umatilla County Survey No. Q-747-A in November, 1960, Wayne O. Harris accepted a fence corner with fences extending North 30 feet, South and East for the corner point.

MONUMENT AND ACCESSORIES FOUND: None. Accepted fence corner intersection and as best remaining evidence of the corner.

MONUMENT MARKING DETAIL:

T4N R36E
S16
1/4 -----
S21
2019
PLS 1106

NAD 83 (2011) epoch 2010.00 Coordinates
International feet units:
N: 791161.92
E: 8756341.44

MONUMENT SET: Set a 5/8 by 24" rebar with 2" aluminum cap 24" in the ground at fence corner intersection. Cap is marked as shown in Monument Marking Detail.

New accessories:

- A 5/8 by 24" rebar with 1 1/4" red plastic cap bears S 88° E, 16.4', set in fence line.
- A 5/8 by 24" rebar with 1 1/4" red plastic cap bears S 02° W, 23.0', set in fence line.
- A 6" Ponderosa Pine bears S 36° W, 37.6' with 3/4" brass washer marked "PLS 1106" nailed to East side center of tree, 1 foot above ground line.
- A 6" Ponderosa Pine bears N 70° W, 24.3' with 3/4" brass washer marked "PLS 1106" nailed to South side center of tree 1 foot above ground line.


Red plastic caps are marked "ORPLS 1106 WAPLS 17372". All rebar accessories have "bearing object" signs wired to them. Nailed "bearing object" signs to the Ponderosa Pine bearing trees and wired "bearing object" signs to the rebar accessories.

Nailed a "Witness" sign to leaning wood fence corner post East of corner monument.


LOCATION AND COMMENTS: Corner is located on top of a bare ridge at fence intersection. Used spencer tape and compass with 18° East declination to measure corner accessories.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal



William R. Wells



renews 6-30-20

\4N36N-11

20-022-R