

ERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E. , W.M.


Corner Code No. R-21

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114 dated July 2, 1992. The original notes state:

Set post corner for Secs. 23, 24, 25 and 26, on hillside facing the East; drove charred stake and made stone mound as per instructions.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 4' diam. mound of stone, with the remains of an old fence extending into it from the South. Wood around mound indicates an old fence jack was at this position. This mound location fits well with recovered corners to the South and East and I accept this location as the best remaining evidence of the original corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe 18" in ground to bedrock and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

There is only one bearing tree within reasonable limits:
A 18" ponderosa pine bears S 83 1/2°W - 96.9', scribed T4N R36E S26 BT. The pine is the most Northerly of two trees growing side by side.

Set reference monuments as follows:
A 5/8" by 15" iron pin bears N 40 1/2°W - 23.0'.
A 5/8" by 15" iron pin bears N 74°E - 13.1'.
A 5/8" by 15" iron pin bears S 42 1/2°E - 16.1'.

Attached Bearing Object signs to bearing tree, and each iron pin reference monument.
Iron pins are capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

Set a steel fence post South of corner with a Witness Corner sign attached.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 7-92
 Rec'd By KK
 No. 92-79-B