


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner was originally established by William O'Dell under contract No. 114 dated July 2, 1866. The original notes state that at the corner a wood post was set in a mound of stones as per instructions from which: A 20" pine bears S10°W 350 lks (231.0 ft).



T-21

Description of corner evidence found:

Found a 36" Ponderosa Pine with opened blaze and some scribing visible. A small mound of stone exists N18°E 236 ft. from the found BT. This mound is approximately 5 feet east of a 6 inch steel pipe set in concrete for a fence corner, fences go east and south. This mound appears to be part of an old fence jack. At the record bearing and distance from the original bearing tree a search was made for the original mound and post. There are a few scattered stones in the vicinity but nothing that could be considered the original mound. The corner position was re-established at the record bearing and distances from the found bearing tree.

Description of monument and accessories established to perpetuate the original location of this corner


At the re-established corner position a 2"x30" iron pipe with brass cap was set 2 inches in the ground and surrounded with a mound of stone. The pipe monument could not be set any deeper due to solid rock. The monument is located S89°W 24.8 ft. from the 6" steel pipe set in concrete for the fence corner.

Established one new bearing tree:

A 14 inch Bull pine bears S9°E 193.6 ft. scribed 1/4 S 25 BT.

This bearing tree also has a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush. Painted a red ring around each BT.

The cap is stamped:



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

William R. Wells

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

This corner was set March 14, 1980.

Office of Surveyor County of Umatilla  
State of Oregon, I hereby certify that the within instrument was filed in this office  
for record on the 27<sup>th</sup> day of March, 1980  
David Brumbein by Betty L. Statts  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor  
Date R-27-80  
Rec'd By ELS  
No. R-46A