

**CE. FILED RECORD OF LAND CORNER MONUMENTATION**

T 4N, R 36E., W.M.

Corner Code No. T-5

Note: Monument marked as shown below

**History of original corner establishment:**


This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a wood post was set from which:

A 20" pine bears S45°E 81 lks.  
A 24" pine bears S63°W 116 lks.

In 1889, during his County Survey No. 46, Surveyor Arnold reestablished the corner from the original bearing trees as follows:

\* I set a basalt stone 19 by 14 by 7 ins. wkd. 1/4 on W. face on gentle S.W. slope from which an original bearing tree, a pine 36 ins. dia., bears S65°W 108 ft. dist., and the stump of an original bearing tree, which has recently been cut down, of about same dia. brs S63°E 54 ft. dist.,

(The discrepancy between the original bearing tree calls and the calls for bearing trees in Co. Survey No. 46 is noted by this surveyor).



Corner No.  
Compass Declination: 19.0°

**Description of corner evidence found:**

Found fence corner with fences running S6°W and east-west. Accepted fence corner as the best remaining evidence of the original corner location. The fence corner also matches, within reasonable limits, the topographic calls of Co. Survey No. 46, to the old road bed north of the corner, and to the ravine to the south of the corner.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At the position of the found fence corner, after a thorough search for the stone set in the 1889 Arnold survey, set a 2 1/2" brass cap on 1 1/2" by 30" galv. iron pipe 24" in the ground and surrounded with a mound of earth and stone from which:

A 18" ponderosa pine bears S89°E 233.5' scribed 1/4 S29 BT.  
A aluminum nail in the west side of Power pole No. 309400 bears N2°W 22.8'.  
The aluminum nail is about 1' above ground.

Attached bearing object signs to the bearing tree and power pole and set a steel fence post west of corner with witness corner sign attached.

The monument is located just north of the fence corner.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

7-27-86

Office of Survey County of Umatilla  
State of OR I hereby certify that the within instrument was filed in this office  
for record on the 28<sup>th</sup> day of July, 1988  
David H. Kumbria by Kathleen K. Ambrose  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 7-88  
Rec'd By [Signature]  
No. 88-42-C